

U.T of Jammu & Kashmir
OFFICE OF THE ASST.EXECUTIVE ENGINEER JAL SHAKTHI(PHE)
SUB-DIVISION POONCH

SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

No. PHE/CSDP/31

Dated: 27-4-2026

It is certified that this office has inspected Carmel School Chaktroo, Poonch on 27-4-2026 and found that the Carmel School Chaktroo has safe drinking water facilities for the students and members of staff of the institution and is maintaining the hygienic sanitation condition in the school building and the campus as per norms prescribed by the U.T Govt.

The above is valid for a period of 1 year time


Assistant Executive Engineer
Jal Shakti (PHE) Civil
Sub Division Poonch
PHE Sub Division Poonch

Copy to the :

Principal, Carmel School Chaktroo

	DISTRICT WATER TESTING LABORATORY POONCH MAIN PUMPING STATION DUNGUS NEAR DAK BUNGLOW POONCH		
	JAL SHAKTI(PHE) DEPARTMENT, UT OF J&K DOC Ref: PHE/WQC/DP/QF-7.8.1		

Sample details

Client Name:	CARMEL SCHOOL CHAKTAROO (CHANOAK)		
Client Ref No:	N/A		
Sample ID :	JSD/WQC/OLP-TO-04-54	Date of Receipt:	21-04-26
Report No:	JSD/WQC/OLP-REP-04-98	Report Date:	23-04-26
Sample Description:	1000ml SAMPLE OF DRINKING WATER IN A PLASTIC BOTTLE		
Test Start Date:	21-04-26	Test End Date:	23-04-26
Test condition	FEASIBLE FORM	RESULT	SATISFACTORY

Test Report					
Physico-Chemical Parameters					
Sr. No.	Parameter	BIS Permissible Limit (mg/l)	Range of Testing as per Scope (mg/l)	Test Results (mg/l)	Test Method
1	pH	6.5 - 8.5	2 - 12	8.04	IS 3025 (Part 11)
2	Colour	15 HU	1 - 100 HU	10	IS 3025 (Part 4)
3	TDS	2000	5 - 1000mg/l	495	IS 3025 (Part 16)
4	Turbidity	5 (NTU)	0.1 - 1000 NTU	3.69	IS 3025 (Part 10)
5	Iron	1.0	0.075 - 5.0	0.01	IS 3025 (Part 53)
6	Chloride	1000	5 - 1000mg/l	49.64	IS 3025 (Part 32)
7	Magnesium	100	1 - 1000mg/l	19.69	IS 3025 (Part 46)
8	Sulphate	400	1 - 1000mg/l	40.69	IS 3025 (Part 24)
9	Calcium	200	5 - 1000mg/l	85.69	IS 3025 (Part 40)
10	Total Hardness	600	5 - 1000mg/l	280	IS 3025 (Part 21)
11	Alkalinity	600	5 - 2000mg/l	190	IS 3025 (Part 23)
12	E.coli	Absent/Present	Absent/Present	ABSENT	H2S Test Vial

Note:

- The test report and result relate to the specimen/ sample (s) of the material as delivered /received and tested in the laboratory.
- This test report shall not be reproduced in part, without the permission of this laboratory. □ Any correction invalidates this test reports.
- WQC lab always strives to provide accurate and reliable for all customers. However, it is not responsible for any financial/legal liability arising of any errors or omissions.

•ADL: Above Detectable Limits, •BDL: Below Detec


 Reviewed/Authorized signatory
 PARAMJIT SINGH (QM/TM)